

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-135-01,011 0002
C SE SW, SEC. 11, T 20 S, R 25 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3447
Operator: Ranken Energy Corporation
Name: Ranken Energy Corporation
Address: 601 N. Kelly, #103
Edmond, OK 73034-3012

Lease Name Neill OWWO Well # 1
County Ness 147.55
Well Total Depth 4540 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 505

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number
Address

Company to plug at: Hour: 9:15 a.m. Day: 9 Month: 4 Year: 19 97
Plugging proposal received from Tom Larson

(company name) Larson Engineering (phone) 316-653-7368

were: 4 1/2" at 4539' w/165 sx cement, PBD 4449', Perfs at 4478-88, 4424-34, 4397-4407, 4377-84,
1st plug pump 25 sx cement with 2 sx hulls on bottom, 4363-66', CIBP @ 4458
2nd plug gel to 1200', cement to surface. DV tool at 1700' w/425 sx cement

Check backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 10 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement with 2 sx hulls on bottom,

2nd plug pumped 130 sx cement down tubing at 1716'-went on vacuum. Shut down.

3rd plug 4/10/97 Ran wireline to cement-TOC 1835', Fluid level at 1490'

Pumped 80 sx cement and filled casing.

Went down backside and pressured up immediately to 500 psi and held.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE APR 22 1997
INV. NO. 47980

Signed Michael J. Moore
(TECHNICIAN)