

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24160-00-00  
Spot: NWSW Sec/Twnshp/Rge: 16-20S-25W  
2011 feet from S Section Line, 550 feet from W Section Line  
Lease/Unit Name: ROWE Well Number: 1  
County: NESS Total Vertical Depth: 4487 feet

Operator License No.: 31900  
Op Name: NOR-WEST KANSAS OIL, L.L.C.  
Address: RR 2, BOX 14  
WAKEENEY, KS 67672

Conductor Pipe: Size feet: \$145.83  
Surface Casing: Size 8.625 feet: 208  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 10/14/2001 1:30 PM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC  
Proposal Rcvd. from: BURT Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 50 SX CMT. 3RD PLUG AT 230' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 10/14/2001 4:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 50 SX CMT. 3RD PLUG AT 230' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Jim Holland (TECHNICIAN)

RECEIVED  
OCT 25 2001  
10-25-01  
KCC WICHITA

INVOICED  
OCT 15 2001  
DATE 10-26-01  
INV. NO. 2002060854

Form 10/15/01