

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24161-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 12-20S-25W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: GRACE Well Number: 1
County: NESS Total Vertical Depth: 4455 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B WEST 10TH STREET
GREAT BEND, KS 67530

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 785
Production: Size feet:
Liner: Size feet:

9144.79

Well Type: DH UIC Docket No: Date/Time to Plug: 10/03/2001 11:45 AM

Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.

Proposal Rcvd. from: DORAN MARGHEIM Company: L.D. DRILLING, INC. Phone: (316) 793-3051

Proposed Plugging Method: 1ST PLUG AT 1660' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 10/03/2001 1:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1660' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Michael J Maier

(TECHNICIAN)

RECEIVED
10-11-01
OCT 11 2001

INVOICED

OCT 04 2001

DATE 10-11-01

NV. NO. 2002060787

KCC WICHITA

Form 1723