

11-25

To: 1 051106
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,307-6760
Approx. S/2 NW NW, SEC. 3, T 20 S, R 25 W/E

4275 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5248
Operator: Olympic Petroleum Company
Name & Address: 2121 South Columbia Avenue
Tulsa, OK 74114

Lease Name Davison Trust Well # 1
County Ness 147.06
Well Total Depth 4525 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor R & C Drilling Company, Inc. License Number 9087
Address P.O. Box 296, Hays, KS 67601

Company to plug at: Hour: 5:15 p.m. Day: 25 Month: 11 Year: 19 88

Plugging proposal received from John Weis

(company name) R & C Drilling Company, Inc. (phone) 913-625-4548
Elevation 2413' GL
were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1669-96'

1st plug at 1696' with 50 sx cement, 2nd plug at 900' with 80 sx cement,
3rd plug at 290' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 p.m. Day: 25 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1696' with 50 sx cement,
2nd plug at 900' with 80 sx cement,
3rd plug at 290' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1988
11-30-88
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.
DEC 8 1988

Signed Richard N. Lacey
(TECHNICIAN)

DATE _____
INV. NO. 23274