


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber

County. Sec. 10 Twp. 32S Rge. 11W (E) (W)

Location as "NE/CNW%SW%" or footage from lines C NW SE NE

Lease Owner Sinclair Oil & Gas Company

Lease Name L. T. Groendycke Well No. 1

Office Address P. O. Box 521, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-25 19 57

Application for plugging filed 1-25 19 57

Application for plugging approved 1-26 19 57

Plugging commenced 1-25 19 57

Plugging completed 1-25 19 57

Reason for abandonment of well or producing formation Dry Hole.

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Verbal approval granted before plugging started.

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 8, Pratt, Kansas.

Producing formation NONE Depth to top Bottom Total Depth of Well 4598' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
NONE				10-3/4"	270'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole 4598' to 250'.
Set Halliburton Cement plug at 250'.
Dumped 25 sks. cement 250' to 210'.
Mudded hole 210' to 30'.
Set Halliburton cement plug at 30'.
Dumped 1/2 sack of hulls.
Dumped 8 sks. of cement 30' to Surface.

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Company
Address 1612 First Natl. Bldg., Tulsa, Oklahoma.

STATE OF Kansas, COUNTY OF Rice, ss.
W. B. Rhees (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


P. O. Box 521, Tulsa, Oklahoma

(Address)

SUBSCRIBED AND SWORN to before me this 30 day of January, 19 57

My commission expires 19 June 1957

Notary Public.



L. T. GROENDYCKE NO. 1
NE/4 of Section 10-32S-11W
Barber County, Kansas
Sinclair Oil and Gas Company

10-3/4" O. D. casing cemented at 276'

Drilling commenced January 4, 1957
Drilling completed January 25, 1957

FROM	TO	FORMATION	REMARKS
0'	70'	Sand rock	
70	145	Sand & clay	
145	245	Clay & shale	
245	276	Shale & lime	10-3/4" O. D. casing cemented at 276'
276	670	Shale & shells	
670	1522	Shale	
1522	1595	Lime & shale	
1595	1815	Lime	
1815	2055	Lime & shale	
2055	2125	Lime	
2125	2311	Lime & shale	
2311	2585	Shale & lime	
2585	2693	Lime & shale	
2693	2845	Shale & lime	
2845	2888	Lime	
2888	3005	Lime & shale	
3005	3110	Shale & lime	
3110	3535	Lime & shale	
3535	3600	Shale & lime	
3600	3609	Sand	
3609	3665	Lime & shale	
3665	3680	Lime	
3680	3705	Sand	
3705	3751	Lime & shale	
3751	3768	Lime - Lansing	
3768	3808	Lime & shale	
3808	4086	Lime	
4086	4116	Lime & shale	
4116	4187	Lime	
4187	4288	Lime & shale	
4288	4315	Lime	
4315	4390	Lime & shale	
4390	4404	Lime & sand	Coring 4396'- 4404'
4404	4444	Lime & shale	Coring 4412'- 4444'
4444	4450	Lime	

PLUGGING	
FILE	SEC 10 T 32 R 11 W
BOOK	PAGE 136 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1957
1-31-57

Sinclair Oil and Gas Company - L. T. Groendycke No. 1 - continued:

Page 2

FROM	TO	FORMATION	REMARKS
4450	4497	Lime & chert	
4497	4507	Chert	
4507	4516	Lime	
4516	4568	Lime & chert	
4568	4598	Chert & lime	Hole plugged

T.D. 4598'

This is a true copy of the driller's log as shown on the drilling tickets.

BARBOUR DRILLING COMPANY

By: *M. E. Barbour*

Subscribed and sworn to before me on this 28th day of January, 1957.

Merry Jane Burt
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

My commission expires: July 27, 1957 JAN 31 1957

COM 1-31-57

PLUGGING	
FILE SEC 10 T 32	11W
BOOK PAGE 136	LI E 28