


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Rush County. Sec. 8 Twp. 19S Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines NW SW NW
Lease Owner J. A. Allison
Lease Name Schon Well No. 1
Office Address 1415 Wichita Plaza Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed February 6, 1970 19
Application for plugging filed August 21, 1970 19
Application for plugging approved August 24, 1970 19
Plugging commenced September 10, 1970 19
Plugging completed September 19, 1970 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3929 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	3927'	2050
				8 5/8" @ 322		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Clean out cellar - unpack braden head - dig deadman holes - rig up. Haul sand, cement & water - sand back to 3900' - dump 4 sx cement. Pull slips - work pipe 22" - shoot @ 3202-3010-2818-2680-2550. Shoot & work pipe @ 2233 & 2050 - pull 2050' 4 1/2" pipe. Pumped 20 sx gel, 3 sx hulls & 130 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
10530 1972
8-30-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ralph Comstock
Address 320 N. Park, Stafford, Ks.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. A. ALLISON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

1415 Wichita Plaza, Wichita
(Address)

September 19 70

January 14, 1974

Frances O. Erhard
Notary Public.



15-165-20146-00-01

B & B DRILLING, INC.

548 Petroleum Building

Wichita, Kansas 67202

February 9, 1970

DRILLERS LOG

Re: Schon #1 Wash Down
NW SW NW Sec. 8-19S-16W
Rush County, Kansas

COMPANY: J. A. Allison
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: February 3, 1970
COMPLETED: February 6, 1970

8 5/8 @ 322

0	35	Cement
35	340	Washing Down
340	3935	Washing Down
3684	3693	Drill Stem Test #1
3523	3532	Drill Stem Test #2
3511	3520	Drill Stem Test #3

Ran 4 1/2" casing @ 3927 w/ 50 sx Poz & 100 sx Common

We certify the above and foregoing to be true and correct copy of the log on the #1 Schon Wash down, located in Rush County, Kansas.

Bice Lohar President

Alma A. Neiser Notary Public

Subscribed and sworn to before me this 9th day of February, 1970. My commission expires May 31, 1970

RECEIVED
STATE CORPORATION COMMISSION
8-24-70
AUG 24 1970
CONSERVATION DIVISION
Wichita, Kansas