

15-1165-20146-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rush County. Sec. 8 Twp. 19S Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines. NW SW NW
Lease Owner Allison & Black
Lease Name Schon Well No. 1
Office Address 1415 Wichita Plaza - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 4-29 19 68
Application for plugging filed 4-29 19 68
Application for plugging approved 4-29 19 68
Plugging commenced 7: PM 4-29 19 68
Plugging completed 1:30 PM 4-29 19 68
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation none Depth to top Bottom Total Depth of Well 3926 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
| | | 0 | 322' | 8 5/8" | 322 | 0 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with drill pipe to 420', cemented with 70 sacks
Fill hole to 40' set plug and hulls and cemented with 10
sacks and 2 sacks in rat hole. at 1:30PM by Leo Massey

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B DRILLING, ZINC.
Address 207 Petroleum Building - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
207 Petroleum Building - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 68

My commission expires May 31, 1970
Notary Public.

15-165-20146-0000

B & B DRILLING, INC.

548 Petroleum Building

Wichita, Kansas 67202

May 3, 1968

DRILLERS LOG

Re: Schon #1
NW SW NW Sec. 8-19S-16W
Rush County, Kansas

COMPANY: Allison & Black
CONTRACTOR: B & B Drilling, Inc.
TOTAL DEPTH: 3926'
COMMENCED: April 19, 1968
COMPLETED: April 29, 1968

| | | | | |
|------|------|----------------|----------|--------|
| 0 | 322 | Clay & Shale | | |
| 322 | 550 | Shale & Shells | | |
| 550 | 800 | Sand | | |
| 800 | 1090 | Red Bed | | |
| 1090 | 1170 | Red Bed | | |
| 1170 | 1200 | Anhydrite | | |
| 1200 | 1450 | Shale & Lime | | |
| 1450 | 1705 | Shale & Lime | | |
| 1705 | 2263 | Lime & Shale | | |
| 2263 | 2585 | Lime & Shale | | |
| 2585 | 3225 | Shale & Lime | | |
| 3225 | 3421 | Lime & Shale | | |
| 3421 | 3526 | Lime | | |
| 3526 | 3612 | Lime & Shale | | |
| 3612 | 3780 | Lime | | |
| 3780 | 3845 | Lime | DST #1 | & #2 |
| 3845 | 3852 | Lime | Arbuckle | DST #3 |
| 3852 | 3864 | Arbuckle | DST #4 | & #5 |
| 3864 | 3915 | Lime | | |
| 3915 | 3926 | Lime | Log | |
| 3926 | | Total Depth | D & A | |

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #1 Schon, located in Rush County, Kansas

Bill Lahar President

Alma G. Muesel Notary Public

Subscribed and sworn to before me this 3rd of May, 1968.

My commission expires May 31, 1970