


15-165-20469-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD

Rush County, Sec. 13 Twp. 19 Rge. 16 (E) (W)



Locate well correctly on above Section Plot

Location as "NE/CNW/SW" or footage from lines C NW NE
Lease Owner Al Tipton
Lease Name Miller #1 Well No. _____
Office Address Hays, Kansas 67601
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19__
Application for plugging filed _____ 19__
Application for plugging approved _____ 19__
Plugging commenced 3/20/75 _____ 19__
Plugging completed 3/24/75 _____ 19__
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3721' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	FROM	TO	SIZE	PUT IN	PULLED OUT
			8-5/8	1037	none
			5 1/2"	3720'	2944'

RECEIVED
STATE CORPORATION COMMISSION
4-9-75
9/14/75
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3600' and dumped 5 sacks cement. Loaded hole with 80 barrels S.W., shot pipe at 3115', 3018', 2921', pulled 134 joints. Set rock bridge from 360 to 350' and dumped 5 yards ready mix.

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss. NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

Subscribed and sworn to before me this 31st day of March 19 75

Margaret Melcher
Notary Public

My commission expires _____
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

15-165-20469-0000

DRILLER'S LOG

COMPANY: Al Tipton, Box 157, Hays, Kansas 67601
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202
 LEASE: #1 S. Miller
 LOCATION: c NW NE 13-19S-16W, Rush County, Kansas
 COMMENCED: June 29, 1973
 COMPLETED: July 9, 1973
 CASING: Set 8 5/8" Surface Casing @ 1037' w/400 sacks cement
 Set 5 1/2" Casing @ 3720' w/100 sacks cement (Used)

0-720	Shale-Sand-Shells
720-1040	Shale & Red Bed
1040-1060	Anhydrite
1060-1940	Shale & Red Bed & Salt
1940-2140	Lime
2140-2290	Lime (Ft. Riley)
2290-2420	Lime
2420-3310	Lime & Shale
3310-3399	Lime w/Shale Streaks
3399-3440	Lime
3440-3529	Lime (L.K.C.)
3529-3687	Lime
3687-3721	Sand
3721	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 6 1975
 3-6-75
 CONSERVATION DIVISION
 TOPEKA, KANSAS

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 S. Miller, located in c NW NE 13-19S-16W, Rush County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, on the 9th day of July, 1973.

Catherine Jarcey
 Notary Public - Catherine Jarcey

NOTARY
 PUBLIC

My Commission Expires:
 March 25, 1976.