

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rush County. Sec. 12 Twp. 19 Rge. 16W E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
SE NE NW

Lease Owner Icer Addis  
Lease Name Damm Well No. 2

Office Address P. O. Drawer 8038, Wichita, Kansas 67208  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed June 13 19 76  
Application for plugging filed June 13 19 76  
Application for plugging approved June 13 19 76  
Plugging commenced June 13 19 76  
Plugging completed June 13 19 76


Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3647'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug @ 400' w/40 sacks 50/50 Pozmix w/4% Gel  
Top plug @ 40' w/1/2 sack hulls and 10 sacks 50/50 Pozmix, 4% Gel.

RECEIVED  
STATE CORPORATION COMMISSION  
6-22-76  
JUN 22 1976

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Wayne Dobbs (employee of owner) or (owner/cooperator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs  
Box 823, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of June, 19 76

Dorothy M. Hague  
Notary Public.

My commission expires April 11, 1978

DRILLERS' WELL LOG

DATE COMMENCED: June 4, 1976  
 DATE COMPLETED: June 13, 1976

Icer Addis  
 DAMM # 2  
 SE NE NW  
 Sec 12-T19-R16W  
 Rush County, Kansas

ELEVATION: 1999 K.B.

0 - 40' Sand  
 40 - 85' Sand and Shale  
 85 - 196' Shale w/sand streaks  
 196 - 465' Shale and Red Bed  
 465 - 499' Dakota Sand  
 499 - 559' Sand  
 559 - 655' Shale  
 655 - 1018' Red Bed  
 1018 - 1052' Anhydrite  
 1052 - 1775' Shale and Shells  
 1775 - 2000' Shale and Lime  
 2000 - 2210' Shale  
 2210 - 2855' Lime and Shale  
 2855 - 2973' Lime  
 2973 - 2992' Shale and Sand  
 2992 - 3231' Lime  
 3231 - 3235' Shale  
 3235 - 3261' Lime  
 3261 - 3299' Shale  
 3299 - 3313' Lime and Shale  
 3313 - 3535' Lime  
 3535 - 3571' Lime and Shale  
 3571 - 3597' Shale, Lime, Chert & Sand  
 3597 - 3647' Sand  
 3647' RTD

ELECTRIC LOG TOPS  
 Anhydrite (Driller) 1018  
 Howard 2919  
 Severy 2973  
 Topeka 2992  
 Heebner 3231  
 Toronto 3247  
 Douglas 3261  
 Brown Lime 3299  
 Kansas City 3313  
 Base K.C. 3535  
 Cong. 3571  
 Regan 3597  
 RTD 3647

SURFACE PIPE:  
 Set used 8 5/8", 28# pipe @ 1024'  
 w/175 sacks 60/40 Pozmix, 2% Gel,  
 2% cc & 200 sacks Common, 2% Gel,  
 3% cc.

A F F I D A V I T

STATE OF KANSAS }  
 COUNTY OF BARTON } ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 18 day of June, 1976.

Dorothy M. Hogue  
 Notary Public

My Commission Expires: April 11, 1978

JUN 18 1976  
 6-22-76