

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,539-00

LEASE NAME Copeland

WELL NUMBER 1

SPOT LOCATION NE SE NE

SEC. 26 TWP 20S RGE 25 KK or (W)

COUNTY Ness

Date Well Completed 4-28-84

Plugging Commenced 8:00 P.M.

Plugging Completed 10:00 P.M.
4-27-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CLYDE M. BECKER

ADDRESS 212 First Nat'l Bldg., Ponca City, Okla. 74601

PHONE # (405) 765-8788 OPERATORS LICENSE NO. 7344

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1, Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 4510'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface Hole	Sand & Shale	0	509	8-5/8"	500.85	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug @1650/50 sx. Plug @960/50 sx. Plug @330/40 sx. Plug @40/10 sx,
10 sx in rat hole. Cement: 160 sx 60/40 Pozmix, 2% Gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor D N B DRILLING, INC.
Address 535 North Oliver, Wichita, Kansas 67208

License No. 5476

RECEIVED
STATE CORPORATION COMMISSION

5-8-84
MAY 08 1984

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

James L. Donelson, Jr. (employee of operator) of Wichita, Kansas
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) James L. Donelson Jr.

(Address) 535 N. Oliver,

Wichita, ks.


SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1984

My Commission expires: September 10, 1984



Ella Priess Notary Public

15 735-22539 0000



D N B Drilling, Inc.

ROTARY CONTRACTOR DRILLING DEALS

J. L. DONELSON, PRES.
(316) 687-5471

535 NORTH OLIVER

WICHITA, KANSAS 67208

DRILLERS' LOG

CLYDE M. BECKER
212 First Nat'l Bldg.
Ponca City, Okla. 74601

Copeland #1
NE SE NE, Sec. 26-20S-25W
Ness County, Kansas

Commenced: 4-20-84
Completed: 4-28-84

Surface Casing: 13 joints 8-5/8" 24#
new, tallied 500.85 set at 509,
cemented w/350 sx 60-40 Pozmix,
2% Gel, 3% cc. Plug down 2:15 A.M.
4-21-84

FORMATION

Sand & Shale
Shale & Sand
Sand & Shale
Shale
Shale & Lime
Lime & Shale
Shale & Lime
Lime & Shale
Shale & Lime
Lime & Shale
Lime
Lime & Shale
Lime & Shale
Lime

DEPTH

0 - 509
509 - 790
790 - 1440
1440 - 2275
2275 - 2570
2570 - 2790
2790 - 2860
2860 - 2900
2900 - 3140
3140 - 3370
3370 - 4340
4340 - 4467
4467 - 4490
4490 - 4510 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson, Jr.
JAMES L. DONELSON, Jr.

RECEIVED
STATE CORPORATION COMMISSION

MAY 08 1984

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 2nd day of May, 1984.

Ella Priess
Ella Priess, Notary Public

My appointment expires:
September 10, 1984

