

15-135-20831-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

		X	

Locate well correctly on above Section Plat

Ness County, Sec. 24 Twp. 20S Rge. (E) 25 (W)
 Location as "NE/CNWKSWK" or footage from lines NW NE
 Lease Owner Twin Western Resources, Inc.
 Lease Name Copeland Well No. #1
 Office Address Farmers & Bankers Building, Wichita, Ks. 67202
 Character of Well (completed as Oil, Gas or Dry Hole) D & A
 Date well completed April 15 1974
 Application for plugging filed (verbally) April 15 1974
 Application for plugging approved (verbally) April 15 1974
 Plugging commenced April 15 1974
 Plugging completed 7:00 p.m., April 15 1974
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
 Producing formation Depth to top Bottom Total Depth of Well 4462' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	397'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug set @ 660' w/60 sx. cement
 2nd plug set @ 300' w/30 sx. cement
 3rd plug set @ 40' w/10 sx. cement

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 21 1974
 S-21-74
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Abercrombie Drilling, Inc.
 Address 801 Union Center, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss.
 Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Jerry A. Langrehr*
 801 Union Center, Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 26th day of April, 1974



Beverly Mann
 Beverly Mann
 Notary Public.

My commission expires

CONTRACTOR'S WELL LOG

15-135-70831-0000

OPERATOR: Twin Western Resources, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Copeland #1
 LOCATION: NW NE Sec. 24-20S-25W
 Ness County, Kansas
 GEOLOGIST: Bill Iverson
 SPUD DATE: April 7, 1974
 COMPLETION DATE: April 15, 1974

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 20 1974
 CONSERVATION DIVISION
 Wichita, Kansas

0	90	Sand and Shale
90	1895	Shale and Sand
1895	2865	Shale with Lime Streaks
2865	3955	Shale and Lime
3955	4462	Lime and Shale
	4462	Rotary Total Depth

Drilled 407' of 12 1/4" hole, set 8 5/8" casing at 397' with 275 sx. common cement w/3% Ca.Cl. and 2% gel. Cement circulated. Plug down @ 8:40 a.m., April 7, 1974.

D & A: 1st plug set @ 660' w/60 sx. cement, 2nd plug set @300' w/30 sx. cement, 3rd plug set @40' w/10 sx. cement. Completed @ 7:00 p.m., April 15, 1974. State Plugger: Leo Massey.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack K. Wharton, Geologist, Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the COPELAND #1, NW NE Section 24-20S-25W, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jack K. Wharton
 Jack K. Wharton
 Geologist

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 26th day of April, 1974.

Beverly Mann
 Beverly Mann - Notary Public

My Commission Expires 1-1-75

