

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

RUSH County. Sec. 33 Twp. 19S Rge. 20W(E) (W)

Location as "NE/CNWxSWx" or footage from lines C SW NW

Lease Owner GEORGE A REED

Lease Name BANNISTER Well No. 1

Office Address 1223 UNION NATIONAL BLDG. WICHITA, KS 67202

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed SEPTEMBER 1 19 70

Application for plugging filed SEPTEMBER 1 19 70

Application for plugging approved SEPTEMBER 1 19 70


Plugging commenced SEPTEMBER 1 19 70

Plugging completed SEPTEMBER 1 19 70

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well LEO F MASSEY, HAYS, KANSAS

Producing formation Depth to top Bottom Total Depth of Well 4395 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	279.96"	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD TO 600'. SET PLUG.
PUT IN 70 SACKS CEMENT. FILLED WITH HEAVY MUD TO 240'. SET PLUG. PUT IN 20 SACKS CEMENT. FILLED WITH HEAVY MUD UP TO 40'. SET PLUG. FILLED TO TOP WITH 1 SACK HULLS AND 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
10-7-70
OCT 7 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING CO.
Address 1107 UNION NATIONAL BLDG., WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G F GALLOWAY (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. GALLOWAY 1107 UNION NATIONAL BLDG.
(Address)

Subscribed and sworn to before me this 4th day of September, 19 70



Phyllis Buchanan
Notary Public.

W E L L L O G

OPERATOR: GEORGE A. REED
 WELL NAME: BANNISTER #1 LOCATION: C SW NW SEC 33-19S-20W
 COUNTY: RUSH STATE: KANSAS
 WELL COMMENCED: AUGUST 24, 1970 WELL COMPLETED: SEPTEMBER 1, 1970
 ELEVATION: 2212 KB TOTAL DEPTH: 4395
 PRODUCTION: DRY & ABANDONED RIG NO: #1
 CASING - 8-5/8": RAN 8 JTS 279.96' NEW 20# W/150 SX QUICKSET
 5-1/2": _____

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	279	SAND & SHALE		
279	830	SHALE	1/2°	1100'
830	1050	SAND		
1050	1412	RED BED	1/4°	1600'
1412	1445	ANHYDRITE		
1445	2135	SHALE & SHELLS	1/2°	2275'
2135	3965	LIME & SHALE		
3965	4035	LIME		
4035	4085	LIME & SHALE		
4085	4315	LIME		
4315	4395	LIME & CHERT		
4395		RTD		

RECEIVED
 STATE CORPORATION COMMISSION
 10-7-70
 OCT 7 1970
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. J. Gaerwan

SUBSCRIBED AND SWORN TO, BEFORE ME, This 4th day of September 1970.

MY COMM. EXP. DEC. 7, 1971

Phyllis Buchanan
 PHYLLIS BUCHANAN - NOTARY PUBLIC

