

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 30 Twp. 19S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines C SW 1/4 SW 1/4  
Lease Owner Pubco Petroleum Corporation  
Lease Name Westermeyer Well No. 30-13  
Office Address Box 567, McCook, Nebraska 69001  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 11-1- 1970  
Application for plugging filed verbally 10-31, formally 11-3- 1970  
Application for plugging approved verbally 10-31-, formally 11-2- 1970  
Plugging commenced 11-1- 1970  
Plugging completed 5:30 a.m. 11-1- 1970  
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes - Mr. Leo Massey

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey  
Producing formation none Depth to top Bottom Total Depth of Well 4498 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Dakota	water	335 est	345 est	8-5/8"	367'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1: Pushed a plug to 600', spotted 70 sx. 50-50 Pozmix 6% gel cement from 300' to 600'.

Plug #2: Spotted 20 sx. 50-50 Pozmix 6% gel cement from 216' to 300'.

Plug #3: Spotted 10 sx. 50-50 Pozmix 6% gel cement from 0' to 40'.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 5 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 830 Sutton Place, Wichita, Kansas

STATE OF Rush COUNTY OF Red Willow, ss.  
Charles W. Sanders (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct.

(Signature) Charles W. Sanders  
Pubco Petroleum Corp., Box 567, McCook, Neb.  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1970

My commission expires September 19, 1973  
Notary Public.

15-165-20359-0000

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

WESTERMEYER #30-13  
SW SW Section 30-19S-20W  
Rush County, Kansas


Commenced: October 23, 1970  
Completed: November 1, 1970

RECEIVED  
STATE CORPORATION COMMISSION  
11-16-70  
NOV 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

OPERATOR - Pubco Petroleum Corporation

DEPTH		FORMATION	REMARKS
From	To		
0	70	Clay	
70	369	Surface clay, shale and shells	Ran 11 joints of 8-5/8" casing, set @ 367' w/240 sacks cement.
369	925	Shale and red bed	
925	1130	Sand	
1130	1500	Shale and red bed	
1500	1530	Anhydrite	
1530	1940	Shale and shells	
1940	2425	Lime and shale	
2425	2600	Lime	
2600	3805	Lime and shale	
3805	4498	Lime	
4498	TD		Dry and abandoned.

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the SW SW Section 30-19S-20W, Rush County, Kansas, to the best of my knowledge and belief.


  
JAMES S. SUTTON, II

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 3 day of November, 1970, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires February 1, 1972.

  
Barbara J. Layton, Notary Public

