

STATE OF KANSAS
STATE CORPORATION COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-165-20618-00-00

LEASE NAME Elmore Ryan

WELL NUMBER 1

660 Ft. from Section Line

510 Ft. from E Section Line

SEC. 30 TWP. 19S RGE. 20W (E) or (W)

COUNTY Rush

Date Well Completed _____

Plugging Commenced 4-15-02

Plugging Completed 4-16-02

RECEIVED

MAY 14 2002

5-14-02

KCC WICHITA

OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd. St. North #300 Wichita, Ks. 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

Michael Maier (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4385'

Give depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	324'	None
				5-1/2"	4377'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each string. Plugged off bottom with sand to 4200' and 5 sacks cement. Shot pipe @650', pumped 80 sacks cement and 2 bbls. of H2O. cement circulated too soon. Plated 8-5/8" to 5-1/2" casing, pumped 65 sacks & circulated out of annulus, squeezed 135 sacks down 5-1/2" casing. Shut in @400#. 60/40 pos. 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed: that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 10th day of May 2002

Notary Public

My Commission Expires:

