

15-165 20228-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rush County. Sec. 30 Twp. 19S Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Pickrell Drilling Company
Lease Name Dehner "B" Well No. 1
Office Address 705 4th Nat'l Bank Bldg, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 31, 19 69
Application for plugging filed March 31, 19 69
Application for plugging approved March 31, 19 69
Plugging commenced March 31, 19 69
Plugging completed March 31, 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4425 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 600'. Set plug. Cemented with 70 sacks cement.


Heavy mud to 240'. Set plug. Cemented with 20 sacks cement.

Heavy mud to 40'. Set plug. Cemented to bottom of cellar with 10 sacks cement. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) C. W. Sebitts, Partner & Attorney-in-Fact
705 4th Nat'l Bank Bldg, Wichita, Ks. 67202
(Address)

Subscribed and sworn to before me this 7th day of April, 19 69

My commission expires May 10, 1970 L. M. Whiting Notary Public.

15-165-20228-0000
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202
Rotary Drilling Commenced 3/21/69

LOCATION: Dehner "B" No. 1
NW NW SE Sec. 30-19S-20W
Rush County, Kansas
Rotary Drilling Completed 3/31/69

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (7 jts.) Used 28# 8 5/8" surface casing set at 250' KB with 160 sacks cement. Complete 6:45 PM, 3/21/69. Circulated.

No oil string was run. D & A, plugged on 3/31/69.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

130	Clay & Post Rock	<u>C. F. S.</u>
220	Shale & Shells	4320'
250	Cement	4325'
675	Shale	4360'
915	Red Bed & Shale	4380'
1115	Sand	4390'
1474	Shale, Shells & Sand Stringers	4400'
1515	Anhydrite	4412'
2345	Shale & Lime	4425'
2440	Lime & Shale	
2650	Lime	
3085	Shale & Lime	<u>Slope Tests</u>
3640	Shale	3000'
4075	Shale & Lime	3500'
4320	Lime & Shale	4000'
4380	Cherokee	
4425	Mississippian, RTD	
		<u>S. L. M.</u>
		4087'

RECEIVED
STATE CORPORATION COMMISSION
4-9-69
APR 9 1969
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this _____ day of April, 1969, before me the undersigned, a Notary Public, in and for the County of _____ State of _____, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
Notary Public
L. M. Whiting