

15-165-20325-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rush County. Sec. 30 Twp. 19S Rge. ~~XX~~ 20W (W)  
NW NE SW

Location as "NE/CNW/SW" or footage from lines  
Lease Owner Pickrell Drilling Co., & Southwest Petro-Chem  
Lease Name Westermeyer "I" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 19 70  
Application for plugging filed June 21 19 70  
Application for plugging approved June 21 19 70  
Plugging commenced June 21 19 70  
Plugging completed June 21 19 70  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	266'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top plug @ 650' w/70 sacks, plug @ 275' w/20 sacks,  
plug @ 40' w/10 sacks cement.


RECEIVED  
STATE CORPORATION COMMISSION  
JUN 25 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June, 19 70



My commission expires January 19, 1973

Esther Lamone  
Notary Public.

15-165-20325-0000  
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Co. & Southwest Petro-Chem. Rotary Drilling Commenced 6/12/70  
705 Fourth National Bank Bldg.  
Wichita, Kansas 67202 Rotary Drilling Completed 6/21/70

LOCATION: Westermeyer "I" No. 1, NW NE SW Section 30-19S-20W,  
Rush County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Ran 10 Jts. 8-5/8" surface casing set @ 266' KB. Cemented with  
150 sacks cement. Completed 3:15 P.M. June 12, 1970. Circulated.  
No oil string run. D & A, Plugged 1:30 A.M. June 21, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

85	Clay & Post Rock	C.F.S.
266	Shale & Shells	4360
850	Shale & Red Bed	4383
945	Blaine & Red Bed	4410
1150	Sand	4430
1170	Shale	4450
1523	Shale - Shells, Red Beds	4460
1562	Anhydrite	4470
1662	Shale - Shells	
2000	Shale	
2350	Shale & Lime	S.L.M.
3045	Lime	Board 4263.38
3435	Lime & Shale	Strap 4262.82
3870	Shale & Lime	.56 Short
4320	Lime	
4390	Lime & Shale & Sand	
4450	Lime - Shale	Slope Tests
4470	Lime, RTD	2000
		2500
		3000
		3500
		4000

RECEIVED  
STATE CORPORATION COMMISSION  
6-29-70  
JUN 29 1970  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 24th day of June, 19 70, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.  
Given under my hand and seal of office the day and year last above written.

My commission expires: Jan. 19, 1973

Esther Lamone  
Esther Lamone Notary Public