

15-135-20493-0000

P

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County. Sec. 1 Twp. 20S Rge. (E) 25(W)

Location as "NE/CNW/SW" or footage from lines C NW NE

Lease Owner Al Tipton

Lease Name Kerr #1 Well No. #1

Office Address Box 157 Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 8, 19 71

Application for plugging filed October 8, 19 71

Application for plugging approved October 8, 19 71


Plugging commenced October 8, 19 71

Plugging completed October 8, 19 71

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4425 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	560	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

50 sx Pozmix @ 720'
25 sx Pozmix @ 400'
Bridge & 10 sx Pozmix @ 40'

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1971
CONSERVATION DIVISION
Wichita, Kansas
10-15-71

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address 100 Park Ave. Building Oklahoma City, Oklahoma 73102

STATE OF Oklahoma, COUNTY OF Oklahoma, ss. Leslie Kite (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 71

My commission expires 4-29-75 Jackie Riley, Notary Public.

WELL LOG

15-13S-20493-0200

Company Al Tipton

Sec. 1 T. 20S R. 25W

Contractor Leben Drilling, Inc.

Loc. C NW NE

Farm Kerr #1

County Ness


Total Depth 4425'

Casing 8 5/8"

Commenced September 30, 1971

Production

Completed October 8, 1971



Figures Indicate Bottom of Formations

0'	-	320'	surface clay - shale
320'	-	395'	sd
395'	-	730'	sh
730'	-	1070'	sh & red bed
1070'	-	1335'	sd
1335'	-	1597'	sh & shells
1597'	-	1637'	anhy
1637'	-	1800'	sh
1800'	-	2500'	sh - lm
2500'	-	2640'	lm & sh
2640'	-	2926'	lm
2926'	-	3260'	sh - lm
3260'	-	3320'	lm & sh
3320'	-	3425'	sh - lm
3425'	-	3790'	lm - sh
3790'	-	3951'	lm
3951'	-	4040'	chert - lm - sh
4040'	-	4115'	lm & chert
4115'	-	4380'	lm
4380'	-	4411'	chert
4411'	-	4425'	chert & lm

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1971
CONSERVATION DIVISION
Wichita, Kansas

State of Oklahoma
County of Oklahoma } SS

I, Leslie Kite of Leben Drilling, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Kerr #1 Well.

Leslie Kite

Subscribed and sworn to before me this 14th day of Oct., 1971

My Commission Expires: 4-29-75
Jackie Peltz