


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ness County. Sec. 23 Twp. 20S Rge. (E) 25 (W)  
Location as "NE/CNW/SW" or footage from lines C/NE NE  
Lease Owner Prospect Oil, Inc.  
Lease Name Fehrenbach Well No. 1  
Office Address 811 Union Center Building, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 15 1968  
Application for plugging filed April 15 1968  
Application for plugging approved April 15 1968  
Plugging commenced April 15 1968  
Plugging completed April 15 1968  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4460' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	288'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole as follows: Plugged at 1550' with 100 sacks of cement and mud to 280'; plugged at 280' with 25 sacks of cement and mud to 40'; plugged at 40' with 10 sacks of cement. Two sacks of cement in rat hole. Plug down at 2:45 P. M. April 15, 1968.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

4-22-68

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Charles W. Steincamp (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp  
P. O. Box 355, Great Bend, Kansas  
(Address)

SUBSCRIBED AND sworn to before me this 16th day of April, 1968

My commission expires December 14, 1969



Elaine H. Taylor  
Elaine H. Taylor Notary Public.

15.135.20138.0000

DRILLERS LOG

#1 Fehrenbach

CASING RECORD:  
283.20' of new 8-5/8"  
surface casing.

COMPANY: Prospect Oil, Inc.

DESCRIPTION: C/NE NE  
Section 23-20S-25W  
Ness County, Kansas

TOTAL DEPTH:  
4460'

COMMENCED: April 2, 1968

ELEVATION: 2359' GR

COMPLETED: April 15, 1968

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay	0	40	Ran 283.20' of new 8-5/8" surface casing; set and cemented at 288' with 170 sacks of common cement and 2% gel. Plug down at 11:15 P. M. April 2, 1968.
Clay & Post Rock	40	70	
Shale, Sand & Red Bed	70	313	
Shale, Shells & Anhydrite	313	995	
Shale & Red Bed	995	1000	
Anhydrite	1000	1013	
Red Bed & Shale	1013	1610	
Shale	1610	1614	
Anhydrite	1614	1626	
Shale & Shells	1626	1945	
Shale & Lime	1945	2572	
Lime	2572	2799	
Lime & Shale	2799	3962	
Lime	3962	4460	

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Total Depth 4460'

D. & A.

Plugged hole as follows: Plugged with 100 sacks of cement at 1550' and mud to 280'; plugged at 280' with 25 sacks of cement and mud to 40'; plugged at 40' with 10 sacks of cement. Two sacks of cement in rat hole. Plug down at 2:45 P. M. April 15, 1968.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp  
Charles W. Steincamp, President

Subscribed and sworn to before me this 16th day of April, 1968.

Elaine H. Taylor  
Elaine H. Taylor, Notary Public

