

15-135-22735-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY NESS SEC. 20 TWP. 20 RGE. 25 W/W
Location as in quarters or footage from lines:
C SE SW

Lease Owner Mull Drilling Company
 Lease Name Slagle Well No. 1
 Office Address 221 N. Main, Ste. 300, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed December 14, 1982
 Application for plugging filed yes
 Plugging commenced December 14, 1982
 Plugging completed December 14, 1982
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom _____ T.D. 4471

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	330	8 5/8"	322	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with 140 sacks 50/50 pozmix, 4% gel, 3% CaCl
 as follows:
 70 sacks @ 1020'
 40 sacks @ 450'
 10 sacks from 0-40' (solid bridge)
 10 sacks in rathole
 10 sacks in mousehole

STATE CORPORATION COMMISSION
 RECEIVED
 DEC 20 1982
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss. of drilling contractor
John Jay Darrah, Jr., President ~~(employee of owner) or (owner or operator)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) John Jay Darrah, Jr.
MALLARD DRILLING CO., INC.
405 Century Plaza, Wichita, Ks
 (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 82

Dianne R. Fowler
 Dianne R. Fowler, Notary Public.

My Commission expires: 8/25/84

DRILLERS LOG

15135-22335-0000

COMPANY: MULL DRILLING COMPANY
 CONTRACTOR: MALLARD DRILLING CO., INC.
 405 Century Plaza
 Wichita, Kansas 67202

WELL NAME: SLAGLE #1
 DESCRIPTION:
 C SE SW
 20-20S-25W

RIG NO.: 1

COUNTY: Ness

TOTAL DEPTH: 4471'

ELEVATION:

COMMENCED: December 7, 1982

COMPLETED: December 14, 1982

CASING RECORD:

8 jts. 8 5/8" new 20# surface

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, sand	0	335	Ran 322' new 20# 8-5/8" surface casing; set and cemented with 210 sacks common cement, 2% gel, 3% CaCl at 330'. Cement circulated. Plug down at 5:00 p.m., December 7, 1982.
Clay and sand	335	1060	
Shale	1060	1140	
Sand	1140	1659	
Anhydrite	1659	1671	
Sand and shale	1671	2290	
Shale and lime	2290	4471	
			Ran 2 drill stem tests.
			Hole plugged with 50/50 pozmix, 4% gel, 3% CaCl, as follows: 70 sacks @ 1020'; 40 sacks @ 450'; hulls and 10 sacks @ 40'; 10 sacks in mousehole; 10 sacks in rathole. Plugging completed at 9:30 a.m., December 14, 1982.

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the #1 Slagle well, to the best of my knowledge.

[Signature]
 John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 17th day of December, 1982.

[Signature]
 Dianne R. Fowler, Notary Public

My Commission Expires:
 August 25, 1984

RECEIVED
 STATE CONSERVATION COMMISSION
 DEC 20 1982
 CONSERVATION DIVISION
 Wichita Kansas