


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Ness County, Sec. 20 Twp. 20 Rge. (E) 25 (W)
Location as "NE/CNW/SW" or footage from lines C/SE SE
Lease Owner Strata Drilling, Inc.
Lease Name Roth Well No. 1
Office Address P. O. Box 355, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 6 19 70
Application for plugging filed May 6 19 70
Application for plugging approved May 6 19 70
Plugging commenced May 6 19 70
Plugging completed May 6 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	288.94'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole as follows: Plugged at 720' with 70 sacks of 60-40 pozmix; plugged at 270' with 20 sacks of pozmix; plugged at 40' with 10 sacks of pozmix. Plug down at 8:45 P. M. May 6, 1970.

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1970

CONSERVATION DIVISION
Wichita, Kansas

5-12-70

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.Charles W. Steincamp(employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp

Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 8th day of May, 19 70

My commission expires

December 14, 1973

Elaine H. Taylor

Notary Public.

D R I L L E R S L O G

#1 Roth

CASING RECORD:
288.94' of new 8-5/8"
surface casing.

COMPANY: Strata Drilling, Inc.
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SE SE
Section 20-20S-25W
Ness County, Kansas

TOTAL DEPTH:
4480'

COMMENCED: April 27, 1970
COMPLETED: May 6, 1970

ELEVATION: 2436' KB

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Shells, Sand & Shale	0	307	Ran 288.94' of new 8-5/8" surface cas- ing; set and cemented at 288.94' with 160 sacks of regular cement, 2% gel and 3% C. C. Plug down at 10:10 P. M. April 27, 1970.
Clay & Shale	307	466	
Shale w/sand streaks & Red Bed	466	1045	
#1 Anhydrite	1045	1060	
Red Bed & Shells	1060	1144	
Dakota Sand	1144	1365	
Red Bed & Shells	1365	1659	
#2 Anhydrite	1659	1670	
Red Bed, Shells, Shale & Broken Lime	1670	2082	
Shale & Lime	2082	2315	
Shale & Lime Streaks	2315	2477	
Broken Lime & Shale	2477	2751	
Lime & Shale Streaks	2751	2920	
Lime & Shale	2920	3767	
Lime & Shale Streaks	3767	3841	
Shale & Lime	3841	3971	
Lime	3971	4087	
Lime & Shale	4087	4193	
Lime	4193	4305	
Lime & Shale	4305	4362	
Lime	4362	4440	
Lime & Chert	4440	4452	
Lime	4452	4462	
Lime & Chert	4462	4480	

Rotary Total Depth 4480'

D. & A.

Plugged as follows: Plugged at 720'
with 70 sacks of 60-40 pozmix; plugged
at 270' with 20 sacks of pozmix; plugged
at 40' with 10 sacks of pozmix. Plug
down at 8:45 P. M. May 6, 1970.

STATE OF KANSAS)
COUNTY OF BARTON) ss.

I certify that this is a true and correct copy of the above log to the best of
my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

My Commission Expires:
December 14, 1973
NOTARY
PUBLIC
ELAINE H. TAYLOR
NORTH KANSAS

Subscribed and sworn to before me this 8th day of May, 1970.

Elaine H. Taylor
Elaine H. Taylor, Notary Public