

15:35:205090000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 19 Twp. 20S Rge. (E) 25 (W)

Location as "NE/CNW/SW" or footage from lines C/NE NE  
Lease Owner Strata Drilling, Inc.  
Lease Name McVickers Well No. 1  
Office Address P. O. Box 355, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 14 19 71  
Application for plugging filed November 14 19 71  
Application for plugging approved November 14 19 71  
Plugging commenced November 14 19 71  
Plugging completed November 14 19 71  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Leo Massey, Hays, Kansas

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4490 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	288.49'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Plugged hole as follows: Plugged at 720' with 70 sacks of common cement; plugged at 270' with 20 sacks of common cement; plugged at 40' with 10 sacks of common cement. Plug down at 7:25 P. M. November 14, 1971.


RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
11-17-71

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Charles W. Steincamp (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp, President  
P. O. Box 355, Great Bend, Kansas  
(Address)

Subscribed and sworn to before me this 16th day of November, 19 71  
Elaine H. Taylor  
Elaine H. Taylor Notary Public.



D R I L L E R S      L O G

15135-20509-0000

#1 McVickers

CASING RECORD:  
282.49' of new 8-5/8"  
surface casing.

COMPANY:      Strata Drilling, Inc.

DESCRIPTION: C/NE NE  
Section 19-20S-25W  
Ness County, Kansas

CONTRACTOR:      Strata Drilling, Inc.

TOTAL DEPTH:  
4490'

COMMENCED:      November 6, 1971

ELEVATION:      2461' RB

COMPLETED:      November 14, 1971

D. & A.

FORMATION	FROM	TO	REMARKS
Clay, Post Rock, Sand & Shale	0	305	Ran 282.49' of new 8-5/8" surface casing; set and cemented at 288.49' with 160 sacks of regular cement, 2% gel and 3% C. C. Plug down at 9:00 P. M. November 6, 1971.
Shale	305	565	
Shale w/Sand Streaks	565	810	
Red Bed, Shale w/Sand Streaks	810	1081	
#1 Anhydrite	1081	1094	
Red Bed, Shale & Shells	1094	1171	
Sand & Shale	1171	1330	
Dakota Sand	1330	1395	
Red Bed & Shale	1395	1688	
#2 Anhydrite	1688	1699	
Red Bed, Shale & Shells	1699	1873	
Lime & Shale	1873	2250	
Shale & Shells	2250	2375	
Lime & Shale	2375	4186	
Lime	4186	4282	
Lime & Shale	4282	4384	
Lime	4384	4475	
Cherty Lime	4475	4481	D. & A.
Lime & Chert	4481	4490	

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Rotary Total Depth 4490'

Plugged hole as follows: Plugged at 720' with 70 sacks of common cement; plugged at 270' with 20 sacks of common cement; plugged at 40' with 10 sacks of common cement. Plug down at 7:25 P. M. November 14, 1971.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

My Commission Expires:  
December 31, 1975



Subscribed and sworn to before me this 17th day of November, 1971.

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public