

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
206 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23,575-0000

LEASE NAME Neill

WELL NUMBER 2-11

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1650 Ft. from S Section Line

3200 Ft. from E Section Line

LEASE OPERATOR Ranken Energy Corporation

SEC. 11 TWP. 20S RGE. 25 (E/W)(W)

ADDRESS 2325 SW 15th Street, Edmond, OK 73013

COUNTY Ness

PHONE#(316) -792-3664 OPERATORS LICENSE NO. 3447

Date Well Completed 6/7/91

Character of Well D&A

Plugging Commenced 6/7/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/7/91

The plugging proposal was approved on 6/7/91 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well loc. attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4520'

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	265'	-0-

JUN 11 1991  
6-11-91  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4520'-1720' 10 sks cement @ 40'  
50 sks cement @ 1720' 15 sks in rathole  
80 sks cement @ 800' 10 sks in mousehole  
40 sks cement @ 290'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ranken Energy Corporation

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

GLENDA R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 91

[Signature]  
Glenda R. Tiffin, Notary Public

My Commission Expires: 2-6-92

15-135-23575-0000

RECEIVED  
STATE CORPORATION COMMISSION

JUN 11 1991

CONSERVATION DIVISION  
Wichita, Kansas

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Ranken Energy Corporation  
2325 SW 15th Street  
Edmond, Oklahoma 73013

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Neill

WELL #2-11

LOCATION: 100' E of C S/2 NE SW  
Section 11-20S-25W  
Ness County, Kansas

LOGGERS TOTAL DEPTH: 4517'

ROTARY TOTAL DEPTH: 4520'

COMMENCED: 5-20-91

CASING: 8-5/8" @ 265' w/145 sks cement

ELEVATION: --

COMPLETED: 6-7-91

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Cedar Hills	1119'	Lansing-Kansas City	3831'
Red Bed	1368'	Base Kansas City	4168'
Anhydrite	1700'	Marmaton	4170'
Shale	1724'	Cherokee	4376'
Heebner	3792'	Mississippi	4452'
Totonto	3810'	R.T.D.	4520'


STATE OF KANSAS )  
                  ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
Kyle B. Branum

Subscribed and sworn to before me on June 10, 1991.

My commission expires: February 6, 1992.



  
Glenda R. Tiffin, Notary Public