

1 030627

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,981-0000

SW NE NW SE, SEC. 23, T 20 S, R 25 (W/E)

2145 feet from (S) section line

1815 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9747

Lease Name Klein Well # 1

Operator: Universal Resources Corp.

County Ness

Name & Address 1125 17th, Suite 1800

Well Total Depth 4480 Mississippi 145.60 feet

Denver, CO 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 533

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 23 Month: December Year: 19 85

Plugging proposal received from Albert Augustine

(company name) Murfin (phone) 316-267-3241

Elevation 2376'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1622-1663'

1st plug at 1650' with 50 sx cement

2nd plug at 990' with 50 sx cement

3rd plug at 570' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:15 am Day: 23 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement, 2nd plug at 990' with 50

sx cement, 3rd plug at 570' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging

DATE DEC 27 1985

INV. NO. 11758

DEC 27 1985
12-27-85
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Durrant (TECHNICIAN)

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 12 12 85
month day year

API Number 15- 135-22,981-6000

OPERATOR: License # 9747
Name Universal Resources Corp.
Address 1125 17th Suite 1800
City/State/Zip Denver, CO 80202
Contact Person David Kranz
Phone 303-296-8091

SW NE NW SE Sec 23 Twp 20 S Rge 25 East West
(location)
2145 Ft North from Southeast Corner of Section
1815 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6033
Name Murfin Drilling Company
City/State Wichita, KS

Nearest lease or unit boundary line 1815 feet.
County Ness
Lease Name Klein Well# 1

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator _____
Well Name _____
Comp Date _____ Old Total Depth _____
Projected Total Depth 4500 feet
Projected Formation at TD Miss.
Expected Producing Formations Miss.

Depth to Bottom of fresh water 100 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 500 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 525 feet
Conductor pipe if any required N/A feet
Ground surface elevation _____ feet MSI.

This Authorization Expires 6-10-86
Approved By RCH 12-10-85

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 12-10-85 Signature of Operator or Agent Rob Ramseyer, Agent for Operator Title Ass't. Drlg. Mgr.
Form C-1 4/84

Albert Ramseyer
Speed 12-13-85
Set 525 + well call later.

PUSHER Albert Augustine
TD 4480 FORMATION Miss
SURFACE PIPE 878 @ 533 -
ANHYDRITE 1642 @ 2376 ELEVATION 2376
STARTING TIME & DATE
COMPLETION TIME & DATE 7:15 AM 12-23-85
1st PLUG @ 1650 FT. W/ 50 SX ALLIED
2nd PLUG @ 990 FT. W/ 50 SX
3rd PLUG @ 570 FT. W/ 40 SX
4th PLUG @ 483 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 10 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ Haul. SX
CEMENT COMPANY ALLIED.
TECHNICIAN
1st Bone Aug.

DEC 27 1985