

1 050158

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,293-A ~~00-01~~

C NE SW , SEC. 10 , T 32 S, R 11 W/X
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Stone "WD" Well # 1

Operator: Hummon Corporation
Name &
Address 400 One Main Place
Wichita, KS 67202

County Barber

Well Total Depth 3805 123.66 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 29 Month: February Year: 1984

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2 set at 3802 PBTB 3730 Perfs 3681

1st plug sand back to 3630 with 5 sx cement dumped on top of sand

2nd plug pump through head with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and pump an additional 100 sx cement

Maximum pressure 550# and shut-in pressure 400#

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:10 pm Day: 29 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 3802' PBTB 3730' Perfs 3681'

1st plug sand back to 3680 with 5 sx cement dumped on top of sand

2nd plug pump through head with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and pumped an additional 100 sx cement

Maximum pressure 550# and shut-in pressure 400#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun. They recovered 2894' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE 3-8-84

MAR 07 1984

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 0595

3-7-84
CONSERVATION DIVISION
Wichita, Kansas