

1 050867

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,149-0000

C NE SW, SEC. 10, T 32 S, R 11 W/E

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8628

Lease Name Credo-Schiff Well # 1

Operator: Credo Petroleum Corporation

County Barber 147.62

Name & Address 1860 Lincoln Street, Suite 1000

Well Total Depth 4542 feet

Denver, CO 80295

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 KS State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 2 Month: 1 Year: 1987

Plugging proposal received from Jerb Ogle

(company name) Red Tiger Drilling Company (phone) 913-625-7993

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 300'

1st plug at 600' with 50 sx cement,

2nd plug at 250' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3 a.m. Day: 2 Month: 1 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,

2nd plug at 270' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION  
1-6-87  
JAN 6 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2%gel 3% cc by B.J. Titan.  
(If additional description is necessary, use BACK of this form.)

**INVOICED** (insert) observe this plugging.

DATE 1-7-87

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 15818

1-2 FEB 10 1987

Starting Date 12 20 86  
month day year

(see rules on reverse side)

API Number 15- 007-22,149-0000

OPERATOR: License # 8628  
Name Credo Petroleum Corporation  
Address 1860 Lincoln Street, Ste. 1000  
City/State/Zip Denver, Colorado 80295  
Contact Person Bruce Faulkner  
Phone 303-830-8500

C NE SW 10 32 S, Rg. 11W X East  
1980 Sec. Twp. S, Rg. 11W X West  
3300 Ft. from South Line of Section  
Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302  
Name Red Tiger Drilling Company  
City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 660 feet  
County Barber

Lease Name Credo-Schiff Well # 1

Well Drilled For: Well Class: Type Equipment:  
X Oil SWD Infield X Mud Rotary  
Gas Inj Pool Ext Air Rotary  
OWWO Expl Wildcat Cable

Ground surface elevation feet MSL

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Depth to bottom of fresh water 145

Depth to bottom of usable water 200

Surface pipe by Alternate: 1 X 2

Surface pipe planned to be set 220

Conductor pipe required N/A

Projected Total Depth 4400 feet

If OWWO: old well info as follows: Red Tiger Drilling Co.  
Operator 1729 KS Bank Bldg  
Well Name Wichita, KS 67202  
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus events and regulations.  
Date 12-17-86 Signature of Operator or Agent Title Owner

For KCC Use: BY RED TIGER DRILLING COMPANY

Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt. 1  
This Authorization Expires 6-8-87 Approved By 12-18-86

Set 220' of 8 5/8 on 12-21-86

Handwritten initials and signatures: RCH/KCC

C NE SW 10 Twp 32 S, Rg. 11W X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ANHY 600' feet depth with 50 SXS  
2nd plug @ 250 40 to 0 feet depth with 40 SXS  
3rd plug @ 40 to 0 feet depth with 10 SXS  
4th plug @ feet depth with SXS of  
5th plug @ feet depth with SXS of  
(2) Rathole with 15 SXS  
(b) Mousehole with N/A SXS

2% gel 3% cc

PUSHER Jerk Ogle  
TD 4542 FORMATION Miss  
SURFACE PIPE 8 5/8 @ 250  
ANHYDRITE 300 ELEVATION  
STARTING TIME & DATE 2:00 am 1-2-87  
COMPLETION TIME & DATE 3:00 am 1-2-87  
1st PLUG @ 600 FT. W/ 50 SXS  
2nd PLUG @ 270 FT. W/ 40 SXS  
3rd PLUG @ 40 FT. W/ 10 SXS  
4th PLUG @ FT. W/ SXS  
RAT HOLE CIRCULATED W/ 15 SXS  
MOUSE HOLE CIRCULATED W/ SXS  
WATER WELL PLUGGED W/ SXS  
CEMENT COMPANY B-J Titan  
TECHNICIAN Larry

STATE CORPORATION COMMISSION  
1-6-87  
JAN 6 1987  
CONSERVATION DIVISION  
Wichita, Kansas