

1 090031

11-18

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,403-0000

SE NE SW, SEC. 26, T 20 S, R 25 W/R

1650 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Schlifke Well # 1-F

Operator: Pickrell Drilling Company, Inc.

County Ness 146.06

Name & Address 110 North Market, Suite 205

Well Total Depth 4494 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 648

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123

Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 6 p.m. Day: 18 Month: 11 Year: 19 89

Plugging proposal received from Doyle Folkerts

(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1621-61'

1st plug at 1665' with 50 sx cement, 2nd plug at 675' with 50 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Mike Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9 p.m. Day: 18 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1665' with 50 sx cement,

2nd plug at 675' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1989
11-27-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-89

INV. NO. 26647

Signed Michael R Wilson
(TECHNICIAN)

EFFECTIVE DATE: 11-13-89 State of Kansas 135-23,403

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 11 ¹³/~~12~~ 89
month day year

SE.. NE.. SW... Sec 26 Twp 20 S, Rg 25 X East
X West

..... 1650 feet from South line of Section
..... 2970 feet from East line of Section
(Note: Locate well on Section Plat Below)

OPERATOR: License # 5123
Name: Pickrell Drilling Company, Inc.
Address: 110 N. Market, Suite 205
City/State/Zip: Wichita, KS. 67202
Contact Person: Larry J. Richardson
Phone: 262-8427

County: Ness
Lease Name: Schlifke Well # 1-F
Field Name: Unknown

CONTRACTOR: License #: 5123
Name: Company Tools

* Is this a Prorated Field? .. yes X no
Target Formation(s): Mississippian, Ft. Scott, Cherokee
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2381 feet MSL
Domestic well within 330 feet: .. yes X no
Municipal well within one mile: .. yes X no
Depth to bottom of fresh water: 200' 300'
Depth to bottom of usable water: 436' 580'
Surface Pipe by Alternate: X 1 .. 2
Length of Surface Pipe Planned to be set: 500' 600'
Length of Conductor pipe required: none
Projected Total Depth: 447.5
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
X well .. farm pond .. other
DWR Permit #: N/A Apply For Permit
Will Cores Be Taken?: .. yes X no
If yes, proposed zone: ..

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWMO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

If OWMO: old well information as follows:
Operator: ..
Well Name: ..
Comp. Date: .. Old Total Depth ..

Directional, Deviated or Horizontal wellbore? .. yes X no
If yes, total depth location: ..


* GUZZLER'S Gulch - Miss (Prorated)
Exp. 5/8/90

AFFIDAVIT

600' Alt. I Req.

Doyle
PUSHER Wally Foxworth
TD 4494 FORMATION Miss
SURFACE PIPE 8 5/8 @ 648
ANHYDRITE 1621-61 ELEVATION
STARTING TIME & DATE 9:14 11-18-89
COMPLETION TIME & DATE
1st PLUG @ 1665 FT. W/ 50 SX
2nd PLUG @ 935 FT. W/ ~~50~~ SX
3rd PLUG @ 675 FT. W/ 540 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 1 SX
WATER WELL PLUGGED W/ 1 SX
CEMENT COMPANY Allhead
TECHNICIAN

SPUD
11-9-89
RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1989
CONSERVATION DIVISION
Wichita, Kansas
Wally Foxworth
TYPE OF CEMENT 60/40 pack 6999



- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.