

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135 22,086-0000  
NE/4, Sec. 24, T 20 S, R 25 W/A  
(SWSWNE) feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5729  
Operator: DYNAMAR ENERGY, Inc  
Name & Address  
DERBY, KS

\_\_\_\_\_ feet from W/E section line  
Lease Name JUST CROSS Well # 1  
County NESS  
Well Total Depth 4508 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 7/8 feet 592

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address 107 W. Fowler, Medicine Lodge, KS, 67104

Company to plug at: Hour: 2:00pm Day: 17 Month: Dec Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Elmo Morganstein  
(company name) Clarke (phone) 886-5665 (3116)

were: sanded bottom to 4300' plus 5 sy cmt on top.  
Recovered 1980' of 5 1/2" Pump 3 sy hulls, 10 sy gel,  
70 sy cmt, 15 sy gel, 1 sy hulls, release plug  
and finish w/ 70 sy cmt. Use 50/50 formix,  
4% gel - 3% C.C.

Signed R. Barluttan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:50pm Day: 17 Month: Dec Year: 19 82

ACTUAL PLUGGING REPORT all plug orders followed except plug  
could not be released as sequence was pumped  
through 2". Cementing by Sun.

Remarks: 5 1/2 @ 4498 - PBTD 4495 - Perfs 4431-36.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 22 1982  
12-22-82  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as stated  
and that I (did / ~~did not~~) observe this plugging.

Signed R. Barluttan  
(TECHNICIAN)

INVOICED  
DATE 12-28-82  
2043-w