

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20618-00-00  
Spot: W2E2NENE Sec/Twnshp/Rge: 30-19S-20W  
660 feet from N Section Line, 510 feet from E Section Line  
Lease/Unit Name: ELMORE-RYAN Well Number: 1  
County: RUSH Total Vertical Depth: 4385 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size feet: 9 1/4 2.51  
Surface Casing: Size 8.625 feet: 324 WITH 200 SX CMT  
Production: Size 5.5 feet: 4377 WITH 175 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/16/2002 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 4200' & 5 SX CMT. 1ST PLUG AT 14\*4' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/16/2002 2:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4350'. PERFS AT 4296-4300'. SANDED TO 4200' & 5 SX CMT WITH DUMP BAILER. SHOT PIPE AT 650'. PUMPED 80 SX CMT & 5 BBL WATER DOWN 5 1/2". CMT PREMATURELY CIRCULATED UP 8 5/8" INDICATING A HOLE. PUMPED DOWN CMT. CIRCULATED UP 8 5/8" X 5 1/2" ANNULUS AFTER 50 SX CMT SHUT IN ANNULUS AND SQUEEZED 150 SX CMT DOWN 5 1/2" CASING. MAXIMUM PRESSURE 600#. SHUT IN AT 400#.

APR 21 2002  
4-21-02  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 4-23-02 APR 19 2002  
INV. NO. 2002061696 NP

ENTER UP 3/3