

1 070164

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,019-0000

NE NW NE, SEC. 2, T 16 S, R 26 (W/E)
4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9937

Lease Name Brown Well # 2-2

Operator: Mallon Oil Company
Name & Address 2850 Security Life Building
Denver, CO 80202

County Ness 148.20

Well Total Depth 4560 Mississippi feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 5:15 pm Day: 4 Month: April Year: 1986

Plugging proposal received from Mort Sherfick

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation N/A Anhydrite 1989'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne (1200) with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Jack L. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:15 pm Day: 4 Month: April Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 2015' with 50 sx cement, 2nd plug at 1209' with 80 sx cement, 3rd plug at 310' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

APR 13 1986
4-13-86
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED
APR 13 1986

observe this plugging.

Signed Dan Grohew
(TECHNICIAN)

DATE _____

INV. NO. 13411 4-4

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 4 1 86 month day year

API Number 15-135-23,019-0000

OPERATOR: License # 9937 Name Mallon Oil Company Address 2850 Security Life Building Denver, Colorado 80202 Contact Person Kevin Fitzgerald Phone (303) 572-1511

NE NW NE Sec. 2 Twp. 16 S, Rg. 26 West 4950 Ft. from South Line of Section 1650 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # Name City/State

Nearest lease or unit boundary line 1650 feet County Ness Lease Name Brown Well # 2-2

Well Drilled For: Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Ground surface elevation feet MSL Domestic well within 330 feet: yes no Municipal well within one mile: yes no Surface pipe by Alternate: 1 2 X Depth to bottom of fresh water 200' Depth to bottom of usable water 1175' Surface pipe planned to be set 250' Projected Total Depth 4550 feet Formation Mississippian

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 3/27/86 Signature of Operator or Agent Title OPERATIONS MANAGER

For KCC Use:

Conductor Pipe Required 9 feet; Minimum Surface Pipe Required 250 feet per 40 This Authorization Expires 3-27-86 Approved By

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ anhydrite BASC 50 feet depth with 60/40 poz 6% gel 2nd plug @ Cheyenne 1200 80 feet depth with 60/40 poz 6% gel 3rd plug @ 280 Salinity/SP 50 feet depth with 60/40 poz 6% gel 4th plug @ 40 SB 10 feet depth with 5th plug @ 15 feet depth with (2) Rathole with 15 sxs (b) Mousehole with 10 sxs

Table with columns: PUSHER, TD, SURFACE PIPE @, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ FT. W/ SX, 2nd PLUG @ FT. W/ SX, 3rd PLUG @ FT. W/ SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY, TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION APR 13 1986 CONSERVATION DIVISION Wichita, Kansas