

1 030955

6-22-88

349

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,371-0000
SE NE SW, SEC. 2, T 16 S, R 26 W/E
1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181
Operator: Donald C. Slawson
Name & Address: 104 South Broadway
Wichita, KS 67202

Lease Name Williamson C Well # 1
County Ness 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Plains Inc. Well Service License Number 4072
Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 10:30 a.m. Day: 22 Month: 6 Year: 1988

Plugging proposal received from Clint Base
(company name) Plains Well Service (phone) 913-798-3995

were: 4 1/2" at 4599' PBD 4548' Perfs at 4516-18, 4521-24' Elevation 2585' GL Anhydrite 2025'
1st plug sand back to 4470' with 4 sx cement on top of sand through bailer,
2nd plug perforate at 1100', squeeze 4 1/2" with 125 sx cement,
3rd plug pump 150 sx cement down annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:50 a.m. Day: 22 Month: 6 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4470' and dumped 4 sx cement on top of sand through bailer,

2nd plug perforated at 1100', squeezed 4 1/2" with 125 sx cement, shut in 300 psi.

3rd plug pumped 150 sx cement down annulus, shut in 250 psi.

7-5-88

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 7-19-88

INV. NO. 21439