

To: 1 070910
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-28
API NUMBER 13-135-21,553-0000
NE SE NE, SEC. 4, T 16 S, R 26 W/E
3630 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7076

Lease Name Thornburg "B" Well # 1
County Ness 147.06
Well Total Depth 4525 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Operator: Black Diamond Oil, Inc.
Name & Address 3004 Broadway Ave.
Hays, KS 67601

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Black Diamond Oil, Inc. License Number 7076
Address 3004 Broadway Ave., Hays, KS 67601

Company to plug at: Hour: 3:30 p.m. Day: 28 Month: 1 Year: 1991

Plugging proposal received from Ken Vehige
(company name) Black Diamond Oil, Inc. (phone) 913-625-5891

were: 4 1/2" at 4516' w/300 sx cement. Open hole at 4516-25', 3 holes 4091-4150'
Squeezed in 1984 at 1750' w/180 sx cement.

1st plug casing volume of cement and 50 sx cement down 4 1/2",
2nd plug 200 sx cement down backside.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 28 Month: 1 Year: 1991

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls and 400 lbs. hulls in first part
of 265 sx cement down 4 1/2". Maximum pressure 600 psi and shut in 100 psi.

2nd plug pumped 235 sx cement down backside. Maximum pressure 400 psi and shut in 50 psi.

28-91
FFR 8 1991

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 2-22-91

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 30804
1-28