

1 090345

10-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,240-0000

W/2 NW, SEC. 3, T 16 S, R 26 W/E
3970 feet from S section line
4640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3122

Operator: Vintage Petroleum, Inc.

Name:

Address 4200 One Williams Ctr.

Tulsa, OK 74172

Lease Name Thornburg "L" Well # 1

County Ness

Well Total Depth 4590 149.17 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well X Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address N. Hwy. 283, Ness City, KS 67560

Company to plug at: Hour: 9:35 a.m. Day: 25 Month: 10 Year: 19 93

Plugging proposal received from Gary

(company name) Vintage (phone) 913-798-2435

Work: 4 1/2" at 4589' w/150 sx cement, PBDT 4544', Perfs at 4505-44'

1st plug set CIBP at 1300', test casing integrity,

2nd plug perforate casing at 1150', pump 80 sx cement,

3rd plug pump 200 sx cement down 4 1/2" X 8 5/8" annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:45 a.m. Day: 25 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 1300', tested casing to 300 lbs.,

2nd plug perforated casing at 1150', pumped 160 sx cement, Maximum pressure 1200 psi and

shut in 30 psi.

3rd plug hooked onto backside and pumped in 215 sx cement. Maximum pressure 350 psi and

shut in 155 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

INVOICED

1 (did / xxxxxxx) observe this plugging.

DATE

11-8-93

INV. NO. 39157 DEC 30 1993

RECEIVED
OCT 28 1993
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Signed (TECHNICIAN)