

1 070278

JAN 0 6 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 200'W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A 15-135-21440-0000
NE NW NE SEC. 4, T 16 S, R 26 W/E
4950 feet from S section line
1850 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Thornburg "N" Well # 2

Operator: Donald C. Slawson
Name & Address 200 Douglas Building
Wichita, KS 67202

County Ness 149.44

Well Total Depth 4598 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 339

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 a.m. Day: 6 Month: 1 Year: 1987

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-659-3165

were: 4 1/2" at 4597' PBD 4535' Perfs at 4499-4505'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,
release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 6 Month: 1 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 4 sx cement on top of sand
through bailer,

2nd plug squeezed well with 200 pounds hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 pounds
hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

STATE CORPORATION COMMISSION
JAN 9 1987

Maximum pressure 500 psi and shut in 200 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2400' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did not observe this plugging.)

DATE 1-20-87

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 15947