


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 1 Twp. 16S Rge. 26 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SE SW
Lease Owner Pickrell Drilling Company
Lease Name Miller "U" Well No. 1
Office Address 705 Fourth National Bank Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 21 19 71
Application for plugging filed October 21 19 71
Application for plugging approved October 21 19 71
Plugging commenced October 21 19 71
Plugging completed October 21 19 71
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 4540 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	233'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug set @ 900' with 70 sacks cement,
plus @ 210' w/20 sacks and plug @ 40' w/10
sacks.

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1971
CONSERVATION DIVISION
Wichita, Kansas
10-29-71

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 71.

My commission expires August 13, 1973

Ruth M. Sullivan Notary Public.



ROTARY DRILLING LOG

15135-20499-0000

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Building
 Wichita, Kansas 67202
 LOCATION: Miller "U" No. 1, C SE SW Sec. 1-16S-26W
 Ness County, Kansas

Rotary Drilling Commenced 10/8/71

Rotary Drilling Completed 10/21/71

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: Run 8 Jts. 8 5/8" surface casing set @ 233' KB. Cemented with 140 sacks cement. Completed 7:45 P.M. Circulated.

No oil string run. D & A, Plugged 6:00 A.M., October 21, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Surface Soil		<u>C. F. S.</u>
235	Shale & Shells		3960
1380	Shale & Sand		3999
1410	Red Beds - Shale		4022
1427	Blain		4080
1480	Shale & Shells		4110
1490	Shale		4140
1785	Sand & Shale		4368
1958	Shale		4411
1975	Anhydrite		4490
1990	Shale		4510
2033	Anhydrite		4528
2140	Shale		4540
2600	Shale - Lime		
3300	Lime		<u>S.L.M.</u>
3620	Lime & Shale	Board	4004.5
3695	Shale & Lime	Strap	3999.0
3831	Lime & Shale		5.5 Difference
4510	Lime		
4525	Mississippi Lime		
4528	Lime		
4540	Mississippi, RTD		

Slope Tests

2000
 2500
 3000
 3500
 4000
 4500

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 29 1971
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS

COUNTY OF SEDGWICK } ss.:

On this 12th day of October, 19 71, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 13, 1973

Ruth M. Sullivan Notary Public

