


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 4 Twp. 16S Rge. x(B) 26 (W)  
Location as "NE/CNW/SW" or footage from lines C SE NW  
Lease Owner Pickrell Drilling Company  
Lease Name Thornburg "A" Well No. 1  
Office Address 705 Fourth National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 4 19 70  
Application for plugging filed April 4 19 70  
Application for plugging approved April 4 19 70  
Plugging commenced April 4 19 70  
Plugging completed April 4 19 70  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4590 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 800' w/70 sacks, plug @ 240' w/20 sacks,  
Plug @ 40' w/10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 9 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
4-9-70

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 7th day of April, 19 70

Esther Lamone  
Notary Public.



COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced 3/22/70  
Rotary Drilling Completed 4/4/70

LOCATION: Thornburg "A" No. 1 C SE NW Section 4-16S-26W,  
Ness County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: Run 11 Jts. 32# 8-5/8" surface casing set @ 250' KB. Cemented with 160 sacks. Completed 1:15 PM March 22, 1970. Circulated.

No oil string run. D & A, Plugged 8:15 A.M. April 4, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Clay & Post Rock		<u>C.F.S.</u>
251	Shale		4095
1430	Shale & Shells		4115
1550	Shale		4145
1620	Sand Stringers & Shale		4170
1790	Sand		4200
2050	Shale		4530
2092	Anhydrite		4540
2670	Shale & Lime		4550
2755	Lime & Shale		4560
2880	Shale & Lime		4590
3085	Lime & Shale		
3189	Shale & Lime		
3300	Lime & Shale		<u>S.L.M.</u>
3500	Shale & Lime	Board	4012.51
3635	Lime & Shale	Strap	4012.11
3730	Shale		.40 Difference
3955	Shale & Lime		
3998	Lime & Shale		<u>Slope Tests</u>
4050	Shale & Lime		2000
4115	Lime & Shale		2500
4145	Lime		3000
4170	Shale & Lime		3500
4205	Lime		4000
4275	Lime & Shale		4500
4405	Lime		
4433	Lime & Shale		
4505	Ft. Scott		
4560	Lime & Shale		
4585	Mississippian		
4590	RTD		

RECEIVED  
STATE CORPORATION COMMISSION  
APR 9 1970  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By C. W. Sebitts Attorney-in-Fact


STATE OF KANSAS  
COUNTY OF SEDGWICK

On this 7th day of April, 1970, before me the undersigned, a Notary Public, in and for

C. W. Sebitts

to me known to be the person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its agent and acknowledged to me that he executed the same as his free and voluntary act and deed, and that he is a duly authorized officer of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



January 19, 1973

Esther Lamone  
Notary Public