

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas


15-007-00375-00-01  
WELL PLUGGING RECORD

Barber

County. Sec. 27 Twp. 30 Rge. 11 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines. NE NE SW  
Lease Owner. Aylward Drilling Company et al  
Lease Name. Mease Well No. 1  
Office Address. 813 1st National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 28 1957  
Application for plugging filed January 28 1957  
Application for plugging approved January 28 1957  
Plugging commenced January 28 1957  
Plugging completed January 28 1957  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production (Gas) July 1956  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4481 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	156'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from 4481' to 200' with Halliburton plug, 1/4 sack of hulls and 25 sacks of cement at 200' to 150'; heavy mud from 150' to 35'; Halliburton plug, 1/4 sack hulls and 10 sacks of cement from 35' to bottom of cellar.

NOTE\*\*\*\*\*

This well was originally drilled to a total depth of 3769' in the Douglas sand; 5 1/2" casing was set at 3759' and the well was produced as a gas well from the Douglas. Original spud date was September 27, 1954 and the pipe was set in the Douglas sand October 7, 1954.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor. Aylward Drilling Company  
Address. 813 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Paul W. Hesse (employee of owner) ~~XXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse

813 1st Nat'l Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of January, 1957

My commission expires December 11, 1957

*Duane D. Jessup*  
Notary Public.

PLUGGING  
FILE SEC 27 T. 30 R. 11 W  
BOOK PAGE 137 LINE 20

FEB 11 1957  
CONSERVATION DIVISION  
Wichita, Kansas

02-01-1957

15-007-00375-00-01

MEASE #1

Casing Record:

8 5/8" - 156'  
5 1/2" - 3759'

Company: Aylward Drilling Company et al  
Contractor: Aylward Drilling Company

Commenced: January 12, 1957  
Completed: January 29, 1957

Location: NE NE SW  
Section 27-30S-11W  
Barber County, Kansas

Elevation: 1781 D.F.

-----  
OLD WELL WORKOVER - This well was drilled deeper to the Mississippian

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sandy Lime & Shale	3769	3861	Lansing 3868
Sand & Shale	3861	3870	Mississippi Chat 4429
Lime - very little shale	3870	3925	
Lime	3925	4255	
Lime & Shale	4255	4365	DST 4396-4410 Open 1 hr.; Rec. 21' very slightly gas cut mud. IBHP 25 $\frac{7}{8}$ - FBHP 25 $\frac{7}{8}$
Shale & some Lime	4365	4410	
Lime	4410	4428	
Miss. Chat	4428	4470	DST 4430-4470 Open 1 hr. Rec. 25' oil specked mud. BHP 45 $\frac{7}{8}$
Lime & Shale	4470	4481 T.D.	

D. & A.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse  
Paul W. Hesse

Subscribed and sworn to before me this 31st day of January, 1957

Duane Jessup  
Notary Public

My commission expires December 11, 1957

PLUGGING  
FILE SEC 27 T 30 R 11 W  
BOOK PAGE 137 LINE 20

RECEIVED  
NOTARY COMMISSION

02-01-1957

BARBER COUNTY DIVISION  
1957

15-007-00375-00-01

MEASE #1

Casing Record:

Company: Aylward Drilling Co. et al

Location:

8-5/8" - 156'  
5-1/2" - 3759'

Contractor: Aylward Drilling Co.

Section 27-30S-11W

NE NE SW

Barber County, Kansas

Commenced: September 27, 1954

Elevation: 1781 D.F.

Completed: October 7, 1954

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface	0	5	
Dry Sand	5	32	
Clay	32	42	
Gravel	42	60	
Sandy clay	60	100	
Gravel	100	105	
Red Bed	105	156	
Redbed Shale & Shells	156	900	
Shale Shells	900	1480	
Lime & Shale	1480	1750	
Lime	1750	1930	
Lime Shale	1930	2025	<u>GEOLOGICAL TOPS</u>
Lime & Shale	2025	2190	Heebner 3676
Lime & Shale	2190	2225	Douglas Sand 3759
Lime & Shale	2225	2260	Rotary Total Depth 3769
Shale & Lime	2260	2360	
Lime	2360	2500	
Lime & Shale	2500	2575	
Lime	2575	2610	
Lime & Shale	2610	2660	
Lime & Shale	2660	2830	
Lime & Shale	2830	2945	
Lime & Shale	2945	3080	D.S.T. 3759-69
Lime & Shale	3080	3235	Open 30 min., gas to surface in
Lime	3235	3332	1 min. Gauged 1,930,000 in 5 min.
Lime & Shale	3332	3350	Gauged 7,130,000 in 15 min.,
Sand & Sandy Lime	3350	3400	gauged 7,600,000 in 30 min.
Lime & Shale	3400	3445	Recovered 70' fluid, not salty,
Shale & Lime	3445	3605	slightly distillate cut. BHP 1390psi.
Sandy Shale & Lime	3605	3710	
Shale Lime & Sand	3710	3769	T.D. Set 5 1/2" Casing at 3759 with 100 Sacks.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

*Paul W. Hesse*

Paul W. Hesse

Subscribed and sworn to before me this 15th day of November, 1954.

*Duane Jessup*  
Notary Public

My Commission Expires: 12-11-57

PLUGGING  
FILE NO. 27 T 30 R 11W  
BOOK PAGE 137 LINE 20

RECEIVED  
STATE CORPORATION COMMISSION

FEB 1 1957

02-01-1957

CONSERVATION DIVISION  
Wichita, Kansas