


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 12 Twp. 20 Rge. 25W ~~25E~~ (W)
Location as "NE/CNWxSWx" or footage from lines C SE SW

Lease Owner Kern-Landes
Lease Name Stick Well No. 4
Office Address Box 115 Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Core Hole
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 19____
Plugging completed February 2, 19 64
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1694 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

No surface pipe - 7 7/8" Core Hole
Circulated hole with heavy mud, displaced 25 sacks cement through drill pipe at 540' - heavy mud to 240', displaced 25 sacks cement through drill pipe at 240', heavy mud to 35', set bridge, hulls and 25 sacks cement to bottom of cellar.

Cementing by Sun Cementing Company

RECEIVED
STATE CORPORATION COMMISSION
4-28-66
APR 28 1966

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Harms Drilling Company & Sun Cementing Company CONSERVATION DIVISION
Address Great Bend, Kansas Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lope Land Landes

SUBSCRIBED AND SWORN to before me this 28th day of April, 1966
Edward S. [unreadable] (Address)

My commission expires 11-5-67 Notary Public.

DRILLERS LOG

15135191670000

COMPANY: Kern-Landes Expl. Co., Inc.
FARM: Stick #4
COMMENCED: January 31, 1964

C SE SW Section 12-203-25W
Ness County, Kansas
COMPLETED: February 2, 1964

Elevation:

0 - 845	shale
845 - 1006	Red bed & shale
1006 - 1025	Anhydrite
1025 - 1097	shale & red bed
1097 - 1317	sand
1317 - 1626	shale & red bed
1626 - 1668	anhydrite
1668 - 1694	shale
1694	Total depth

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1966

CONSERVATION DIVISION
TOPEKA, KANSAS

RAN electric log

DRY, plugged, and abandoned.

AFFIDAVIT

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, Allan Harms of the Harms Drilling Company being first duly sworn on oath state:
I have knowledge of the facts, statements and matters herein contained and the same
are true and correct.

Allan Harms
Allan Harms

Subscribed and sworn to before me this 26th day of February, 1964.

Helen E. Gearhart
Helen E. Gearhart - Notary Public

My commission expires: January 22, 1966