

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ness SEC. 16 TWP. 20S RGE. 25W E/W  
Location as in quarters or footage from lines:

C SE SE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Floyd E. Kelly

Lease Name Scott #1 Well No. \_\_\_\_\_

Office Address P.O. Box 415 Plainville, Kansas 67663

Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_

Date Well Completed \_\_\_\_\_

Application for plugging filed \_\_\_\_\_

Plugging commenced 8-17-81

Plugging completed 8-21-81

Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	287'	none
				5-1/2"	4474'	2410'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Moved in on location, got 12" stretch. Plugged off bottm with 1 barrel sand, 5 sacks cement. Shot Pipe @3515', 3341', 3213', 3087', 2964', 2835', 2705', 2577' & 2450'. Pulled 72 joints pipe. Plugged well with 5 sacks hulls, 27 sacks gel, 140 sacks 50/50 pos, 6% gel, 3% cc. Plugging completed.~~

RECEIVED  
STATE CORPORATION COMMISSION  
1 AUG 27 1981  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
R. Darrell Kelso  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 81

My Commission expires:



Irene Hoover  
Notary Public.