

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

CP4

API NUMBER 15-135-24160-0000

LEASE NAME Rowe

WELL NUMBER 1

2,011 Ft. from S Section Line

550 Ft. from ^WX Section Line

SEC. 16 TWP. 20 RGE. 25 (X) or (W)

COUNTY Ness

Date Well Completed 10-14-01

Plugging Commenced 10-14-01

Plugging Completed 10-14-01

RECEIVED

OCT 23 2001
10-23-01
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nor-West Kansas Oil, LLC

ADDRESS R.R. 2, Box 14, Wakeeney, KS 67612

PHONE (785) 743-2769 OPERATORS LICENSE NO. 31900

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-14-01 (date)

by Jim Holland (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4,487'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|-----------------|
| | | | | 8 5/8" | 208' | Cmtd. w/150 sax |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Push bridge plug to 1,700', pump 50 sax cement on plug; push bridge plug to 800', pump 50 sax cement on plug; push bridge plug to 230', pump 40 sax cement on plug; push wiper plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nor-West Kansas Oil, LLC

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor
(Employee of ~~Operator~~) or ~~Operator~~
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 18th day of October, ~~2001~~ 2001

Ruth Phillips
Notary Public

My Commission Expires: _____

