

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-00268-00-00  
Spot: SESENE Sec/Twnshp/Rge: 10-32S-7E  
2925 feet from S Section Line, 327 feet from E Section Line  
Lease Name: BEAMER Well #: 1 WSW  
County: COWLEY Total Vertical Depth: 2210 feet

Operator License No.: 33711

Op Name: B-C STEEL, LLC

Address: 209 N FRY ST  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2210		200 SX
SURF	8.625	80		75 SX

Well Type: WSW

UIC Docket No:

Date/Time to Plug: 06/21/2013 8:00 AM

Plug Co. License No.: 31074

Plug Co. Name: BRAKE, JOE DBA BRAKE INC.

Proposal Rcvd. from: RON WHITEMAN

Company: GENDOR OIL CO

Phone: (620) 467-2615

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 06/28/2013 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 1590', DUMP BAILED 6 SXS CEMENT ON TOP. TAGGED BTM PLUG @ 1555'. CEMENT @ SURFACE ON BACKSIDE OF 5 1/2" CASING. RIH W/TBG @ 350', BRAKE OIL PUMPED 60 SXS 60/40 POZMIC TO SURFACE. 6-28-2013, TAGGED CEMENT @ 85', RIH W/TBG @ 82', BRAKE OIL PUMPED 20 SXS 60/40 POZMIC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM. 6-28-2013. DANIELS READY MIX TICKET #028507 & 028547.

Perfs:

Top	Bot	Thru	Comments
1728	1730	CSG	

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE / 10 YEAR RULE

AUG 23 2013

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

Duane Krueger  
8/23/13

(TECHNICIAN)

1/2K