

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19043-00-00
Spot: NESENW Sec/Twnshp/Rge: 10-32S-7E
3569 feet from S Section Line, 2964 feet from E Section Line
Lease Name: GANE Well #: 1
County: COWLEY Total Vertical Depth: 2839 feet

Operator License No.: 33711

Op Name: B-C STEEL, LLC

Address: 209 N FRY ST
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2845	363	200 SX
SURF	8.5	300		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2013 8:00 AM

Plug Co. License No.: 31074 Plug Co. Name: BRAKE, JOE DBA BRAKE INC.

Proposal Rcvd. from: RON WHITEMAN Company: GENDOR OIL CO Phone: (620) 467-2615

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: PARTIAL

Date/Time Plugging Completed: 06/28/2013 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2060', DUMP BAILED 5 SXS CEMENT ON TOP. TAGGED BOTTOM PLUG @ 2030'. RIH ON WIRELINE CUT CASING @ 363', LAYED DOWN CASING. RIH W/TBG @ 350', BRAKE OIL PUMPED 140 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-2-2013. DANIELS READY MIX TICKET #028552. 7-2-2013, TOPPED WELL BACK TO SURFACE W/20 SXS, TICKET #028569.

Perfs:

Top	Bot	Thru	Comments
2118	2122		CSG

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE / 10 YR RULE


AUG 23 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed


8/23/13 (TECHNICIAN)