

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-35739-00-00
Spot: NWNENW Sec/Twnshp/Rge: 30-21S-8W
4886 feet from S Section Line, 3632 feet from E Section Line
Lease Name: FITZPATRICK Well #: 2
County: RICE Total Vertical Depth: 3450 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR	4.5	1980		
PROD	4.5	3416		125 SX
RBP	4.5	3190		
SURF	8.625	200		180 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/09/2013 12:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM LLC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 08/09/2013 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, START WORKING ON WELL, SET CIBP AT 3190' AND 2 SX'S ON TOP -- SQUEEZED AT 2119' WITH 300 SX'S, PUMPED THRU TUBING AND PACKER. GOT PACKER HUNG AT 1980' WITH SEVERAL JOINTS OF TUBING. DECISION MADE TO PLUG WELL. PERFORATE AT 1150', 700', AND 250'. RUN TUBING TO 1150' AND PUMP 50 SX'S COMMON CEMENT WITH 2% CC - LET SET FOR 1 HR - TAGGED AT 1050', PULL TUBING TO 700' AND PUMP 35 SX'S, PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3346	3352	CSG	
3320	3330	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: 60-40 POZ, 45 GEL. COPELAND TICKET #42059.

AUG 22 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Virgil Clothier
8/29/13 (TECHNICIAN)