

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-21814-00-02  
Spot: SWNENE Sec/Twnshp/Rge: 24-31S-2W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: RENN Well #: 2  
County: SUMNER Total Vertical Depth: 3776 feet

Operator License No.: 30375  
Op Name: GRESSEL, DEWEY H.  
Address: 322 W 20TH ST S  
WELLINGTON, KS 67152

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3776		125 SX
SURF	8.625	425		295 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2013 10:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OFS Phone: (620) 968-7248

Proposed Plugging Method: CIBP 50' ABOVE PERFS - PERF 4 HOLES AT 475' & CIRC CEMENT TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/17/2013 10:00 AM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

SET CIBP AT 3750' & 2 SKS CEMENT. NO RECOVERY. PERF'D CASING AT 475' WITH 4 HOLES. CIRCULATED 215 SKS CEMENT TO SURFACE - CEMENT FELL, WILL TOP OFF WITH REDI MIX SLURRY.

**Perfs:**

Top	Bot	Thru	Comments
3771	3772	CSG	


RECEIVED  
KANSAS CORPORATION COMMISSION  
**AUG 27 2013**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENT & ACID 60/40 % 1 1/4 YARDS REDI MIX -- LOST LEASE

Plugged through: CSG

District: 02

Signed



8/29/13

(TECHNICIAN)