

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-09663-00-00  
Spot: SWNWESW Sec/Twnshp/Rge: 36-19S-12W  
2189 feet from S Section Line, 3803 feet from E Section Line  
Lease Name: BIRZER FLORA Well #: 5  
County: BARTON Total Vertical Depth: 3332 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S YALE # 702  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3328		175 SX
SURF	8.625	137		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/01/2013 9:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER Phone: (620) 793-9556

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/01/2013 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 585' and 125'.  
Ran tubing to 3300' and pumped 14 sx gel, 60 sx cement w/200 # hulls.  
Pulled tubing to 1350' and pumped 70 sx cement w/200 # hulls.  
Pulled tubing to 590' and pumped 250 sx cement w/100 # hulls. Ran out of cement and shut down for 2 hours.  
Pumped 120 sx cement. Circulated cement out casing.  
Pulled tubing. Tied to casing and circulated cement out surface pipe with 25 sx cement.

GPS: 38.35396 -09860326

Perfs:

Top	Bot	Thru	Comments
3328	3333		
3108	3305		
2917	2923		

Remarks: ALLIED CEMENTING

Plugged through: ESG TGL

KCC WICHITA

AUG 15 2013

RECEIVED

District: 04

Signed Bruce Rodie  
8/21/13 (TECHNICIAN)

CM

AUG 08 2013