

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-21130-00-00
Spot: SWNWSWNE Sec/Twnshp/Rge: 10-2S-39W
1770 feet from N Section Line, 2430 feet from E Section Line
Lease Name: HAM Well #: 32-10
County: CHEYENNE Total Vertical Depth: 1341 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1330		80 SX
SURF	7	155		74 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/13/2013 11:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: GERALD LAUER Company: BASIC ENERGY SERVICES, LP Phone: (970) 630-4243

Proposed Pump through 4 1/2" casing. 10 BBL of water prior to 30 sx 50/50 pozmix cement, 1.07 yeild w/1/2 bag of hulls in first 5 sx
Plugging cement. Displaced w/8 bbl of gel water. Pump 30 sx of 50/50 pozmix cement, 1.07 yeild. Look for returns, mix and pump
Method: 5 sx cement, 1.07 yeild into back side of 4 1/2" casing. 7" casing look for fill up.

Plugging Proposal Received By: TOM CULLEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2013 11:30 AM KCC Agent: TOM CULLEY

Actual Plugging Report:

Bison Cementing tied on to 4 1/2" casing and pumped 10 bbl of water, 30 sx cement, 1.07 yeild w/1/2 bag of hulls in the first 5 sx cement. Displaced w/8 bbl of gel water, mixed 30 sx cement, 1.07 yeild and saw cement returns.
Mixed and pumped 5 sx cement, 1.07 yeild down back side of 4 1/2" casing. Between 4 1/2" and 7" casing, had cmeent returns. Pumped a total of 65 sx cement. Bottom plug at 1160' to 802'. Top plug at 299' to top surface.

GPS: 39.89660 -101.68181

Perfs:

Top	Bot	Thru	Comments
1125	1160		NIOBRARA

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: BASIC ENERGY SERVICES

AUG 28 2013

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed _____

9/05/13

(TECHNICIAN)

CM

AUG 21 2013