

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-023-21126-00-00  
Spot: N2SWSWNE Sec/Twnshp/Rge: 12-2S-39W  
2260 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: KELLER FARMS Well #: 32-12  
County: CHEYENNE Total Vertical Depth: 1472 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 1625 BROADWAY, STE 2200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1491		84 SX
SURF	7	203		58 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/13/2013 12:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TOM THOMAS Company: BASIC ENERGY SERVICES Phone: (970) 630-4243

Proposed Plugging Method: Tied on to 2 3/8" tubing and pumped 10 bbl of water ahead of 9.5 bbl gel water. Mixed and pumped 30 sx 50/50 pozmix cement, 1.07 yeild, 15.2 # per gal w/1/2 bag hulls in first 5 sx cement. Pulled tubing to 331' and pumped 30 sx 50/50 pozmix cement, 1.07 yeild, 15.2 # per gal. Filled back side 4 1/2" casing to capacity.

Plugging Proposal Received By: TOM CULLEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/13/2013 12:30 PM KCC Agent: TOM CULLEY

Actual Plugging Report:

Bison Cementing tied on to 2 3/8" tubing w/40 joints in hole at 1232' with a J-55 tubing containment tool. Pumped 10 bbl water in advance of 9.5 bbl of gel water followed by 30 sx 50/50 pozmix cement, 1.07 yeild with 1/2 bag of hulls in the first 5 sx cement. Pulled tubing to 331' and pumped 30 sx cement, 1.07 yeild. Had cement returns, Annulus of well bore between 4 1/2" and 7" casing was full of cement. Topped off well bore with cement. Bottom plug at 1280' to 922' (358' plug) Top plug at 331' to top surface. Total cement 60 sx.

Perforations: 1248' - 1280'  
GPS: 39.89255 -101.64722

Perfs:

Top	Bot	Thru	Comments
1243	1268		NIOBRARA

Remarks: BASIC

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

9/15/13 Tom Culey  
(TECHNICIAN) CM

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 28 2013

CONSERVATION DIVISION  
WICHITA, KS

AUG 19 2013