

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20442-00-00  
Spot: SWNWSWSW Sec/Twnshp/Rge: 11-19S-11W  
890 feet from S Section Line, 317 feet from W Section Line  
Lease Name: BIRZER Well #: 1-V  
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 34320  
Op Name: LASSO ENERGY LLC  
Address: PO BOX 465  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3370		125 SX
SURF	8.625	250		190 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/24/2013 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: BRUCE D. KELSO Company: LASSO ENERGY, LLC. Phone: (620) 259-4000

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/200 # hulls.  
Perforations: 240', 650', 975' and 1300'.  
Sanded off bottom and spotted 5 sx cement on top. 07/23/2013  
Tried to recover pipe but could not.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/24/2013 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Tried to pull pipe. Could not perforate casing.  
Ran tubing to 1350' and pumped 70 sx cement w/100 # hulls.  
Pulled tubing to 650' and pumped 120 sx cement w/100 # hulls.  
Cement circulated. Shut in back side.  
Pumped 180 sx cement and circulated out the braden head. Shut in maximum pressure 350 psi.  
Checked fill up on 07/25/2013. Casing down 5'.

Perfs:

Top	Bot	Thru	Comments
3361	3364		
3320	3328		
3283	3286		
3183	3186		
3132	3136		
3091	3096		
3070	3073		

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: COPELAND ACID AND CEMENTING TICKET # 41096

**AUG 02 2013**

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Ray Dinkel  
8/20/13 (TECHNICIAN) CM

JUL 30 2013