

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20049-00-02
Spot: SENWSE Sec/Twnshp/Rge: 9-5S-13E
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HERMESCH Well #: 1-A
County: NEMAHA Total Vertical Depth: 3898 feet

Operator License No.: 34232
Op Name: MUSTANG FUEL CORPORATION
Address: 9800 N. OKLAHOMA AVE.
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3898	285	
SURF	10.75	352		
T1	2.875	3645	3645	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2013 12:00 PM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: JASON GOSS, CONSULTIN Company: GLACIER PETROLEUM CO., INC. Phone: (405) 830-8365

Proposed Plugging Method: 50' CEMENT PLUG OVER PERFS @ 3571-3621, RECOVER AS MUCH 7" CSG AS POSSIBLE, SET 50' PLUG OVER KS CITY 1150-1200', THEN CEMENT FROM 400' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 02/12/2013 3:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

PERFORATED THE CASING AT 1145' AND 400'. RAN TUBING TO 1148' AND PUMPED 20 SACKS OF CEMENT. PULLED THE TUBING TO 401' AND PUMPED 215 SACKS OF CEMENT TO THE SURFACE.

Perfs:

RECEIVED
AUG 21 2013
KCC Chanute Dist. #3

TH

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks:

Plugged through: TBG

AUG 23 2013

CONSERVATION DIVISION
WICHITA, KS

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

✓ 8/22/13