

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24377-00-00
Spot: SWNESE Sec/Twnshp/Rge: 17-35S-3E
2210 feet from S Section Line, 530 feet from E Section Line
Lease Name: RIPPE Well #: 1
County: COWLEY Total Vertical Depth: 3730 feet

Operator License No.: 34461
Op Name: CRECO OPERATING, LLC
Address: 211 N ROBINSON AVE, STE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3200		
CIBP	5.5	3530		
PROD	5.5	3708		275 SX
SURF	8.625	322		200 SX
SURF	8.625	325		200 SX
T1	2.875	3158		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2013 8:00 AM
Plug Co. License No.: 34461 Plug Co. Name: CRECO OPERATING, LLC
Proposal Rcvd. from: JIM ALLEN Company: CRECO OPERATING LLC Phone: (405) 606-7481

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 3050 W/2 SXS / CIRC 375-0

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2013 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

DUG OUT CELLER. RIH ON WIRELINE SET CIBP @ 3050', DUMP BAILED 2 SXS CEMENT ON TOP OF CIBP. PRESSURED CASING, HELD OK. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 375', SWEDGED INTO 5 1/2" CASING, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 6-11-2013, 2:00 PM. CEMENT TICKET #5220000614.

Perfs:

Top	Bot	Thru	Comments
3546	3551	CSG	
3228	3236	CSG	
3100	3133	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks:

Plugged through: TBG

AUG 22 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed: Duane Krueger
8/23/13 (TECHNICIAN)
JK