

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-04966-00-00
Spot: NWSWSESW Sec/Twnshp/Rge: 18-20S-9W
374 feet from S Section Line, 3735 feet from E Section Line
Lease Name: HECKEL Well #: 2
County: RICE Total Vertical Depth: 3371 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3371		200 SXS CEMENT
PROD	5.5	3345		100 SX
SURF	8.625	198		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2013 11:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-0895

Proposed
Plugging
Method:

According to the rules and regulations of the State of Kansas. 4-1/2" Liner Set @3371' w/200 sxs, cement

Plugging Proposal Received By: HUNTER CLARK WitnessType: PARTIAL
Date/Time Plugging Completed: 08/02/2013 1:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3182' AND CAP WITH 4 SX'S CEMENT.
PERFORATE AT 1250', 850' AND 250'. RAN TUBING TO 1250' AND PUMP 35 SX'S
CEMENT, PULL TUBING TO 850' AND PUMP 35 SX CEMENT, PULL TUBING TO 250'
AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3360	3362	CSG	
3254	3255	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 22 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS #7568. COPELAND #41354

Plugged through: TBG

District: 02

Signed

Virgil Clothier
8/29/13
(TECHNICIAN)